

TEST ATTESTATION


Contract No 1312/2019/2/O - BF

21 January 2020
STG/ESK

Customer Hermann Otto GmbH
Krankenhausstr. 14
DE-83413 Fridolfing

Subject Water accumulation test of the window connection system
"MB 2K with Tape VF" according to the guidelines for
construction sealant - connection to floor-to-ceiling
windows and doors - Part 2 Conduct

Result With regard to the report 1312/19/2/O Holzforschung Austria
hereby confirms, that the accumulating water connection system
"MB 2K with Tape VF", consisting of



Window connection system

- OTTOSEAL® M360 (external) hybrid sealant,
- OTTOSEAL® M361 (internal) hybrid sealant,
- OTTO Primer 1225 adhesive primer,
- OTTOCORD PE-B2 cord,

accumulating water connection system

- Remmers MB 2K flexible, polymer-modified coating,
- Remmers Tape VF 120 joint tape and
- Remmers Tape VF 100 IC inner corner,

meets the test requirements for the guidelines on construction sealants - connection to floor-to-ceiling windows and doors - Part 2, section 5.

Period of validity --

HOLZFORSCHUNG AUSTRIA

DI Georg Steiner
Technical consultant

DI (FH) Jens Schöne

This document was approved electronically in accordance with an internal HFA process by the designated authorized signatory, traceable and documented.

In case of dispute the original German version prevails. This translation is for information purposes only.